

**कार्यालय, कार्यपालन अभियंता जिला निर्माण समिति,
जिला बलरामपुर-रामानुजगंज (छ0ग0)
अल्पकालीन निविदा द्वितीय आमंत्रण सूचना**

निविदा ज्ञाप.क्रं./02/जि.नि.स./2017-18

बलरामपुर, दिनांक 04.10.2017

छत्तीसगढ़ के राज्यपाल की ओर से प्रपत्र "ए" पर निविदा आमंत्रण तिथि तक समस्त संशोधन सहित (दिनांक 01.07.2015 से लागू एस.ओ.आर.) छत्तीसगढ़ के उपयुक्त श्रेणी में पंजीकृत ठेकेदारों को निम्नलिखित कार्य हेतु दो लिफाफा पद्धति के अनुरूप मुंहर बंद निविदायें स्पीड पोस्ट सर्विस द्वारा दिनांक 16.10.2017 को सायं 5.30 बजे तक अधोहस्ताक्षरकर्ता के कार्यालय में प्राप्त की जायेगी। निविदा दिनांक 17.10.2017 को सुबह 11.30 बजे या अवकाश होने की स्थिति में अगले कार्यालयीन दिवस में उपस्थित ठेकेदारों के समक्ष खोली जावेगी।

निविदा अधोहस्ताक्षरकर्ता के कार्यालय में आवेदन पत्र के साथ ठेकेदारों को उपयुक्त प्रपत्र में बैंक सालवेंसी जो 12 माह से पुरानी न हो, जी.एस.टी. पंजीयन आयकर एवं वाणिज्यकर समाशोधन चुकता प्रमाण पत्र वर्ष 2016-17 आदि के साथ नगद भुगतान कर दिनांक 11.10.2017 तक तथा इसके पूर्व कार्यालयीन समय पर प्राप्त किया जा सकता है।

इस कार्य हेतु - निविदा प्रपत्र का मूल्य रुपये 750/- अमानत राशि रुपये 63465/- बैंक सालवेंसी रुपये 1269300/- कार्य पूर्ण करने की अवधि कार्यादेश जारी होने के तिथि से 2 माह (वर्षा ऋतु सहित) एवं सक्षम ठेकेदार - एकल पंजीयन की श्रेणी अ से द तक विद्युत कार्य सहित।

क्र०	कार्य का नाम	कार्य की अनुमानित राशि (लाख में)
1	2	3
1	जिला मुख्यालय बलरामपुर में हाई स्कूल से सेमरी चौक (न्यू कलेक्ट्रेट) एवं थाना चौक से सब्जी मण्डी तक विद्युतीकरण (स्ट्रीट लाईट) लगाने हेतु।	84.62

शर्तें एवं जानकारियां :-

1. अमानत राशि का समायोजन नहीं किया जावेगा, अमानत राशि किसी भी राष्ट्रीयकृत बैंक का होना अनिवार्य है, जो निविदा जारी होने की तिथि से मान्य किया जायेगा।
2. निविदा प्रपत्र के लिये आवेदन पत्र के साथ ठेकेदार का जीवित पंजीयन, समान प्रकृति के शासकीय/अर्धशासकीय कार्यों का अनुभव, आयकर चुकता प्रमाण पत्र, जी.एस.टी. का पंजीयन तथा वाणिज्य कर समाशोधन चुकता प्रमाण पत्र वर्ष 2016-17, बैंक सालवेंसी, श्रमिक पंजीयन की प्रमाणित छायाप्रति संलग्न होना अनिवार्य है एवं मूल प्रमाण पत्रों से मिलान करावें अपूर्ण दस्तावेजों के कारण आवेदन पत्र को निविदा प्रपत्र के लिये मान्य नहीं किया जावेगा।
3. उपरोक्त कार्य निर्धारित समय सीमा में पूर्ण करना होगा एवं समानुपातिक प्रगति देना होगा अन्यथा कार्य को उनके व्यय एवं जोखिम पर बिना समय दिये समाप्त कर दिया जायेगा।
4. अन्य जानकारी कार्यालयीन दिवस में कार्यालय से प्राप्त की जा सकती है।
5. निविदा तिथि से किसी भी दिन अवकाश होने पर अगली तिथि को कार्यवाही की जायेगी।
6. समस्त देयकों का भुगतान जिला निर्माण समिति बलरामपुर के द्वारा किया जावेगा।
7. कार्य से संबंधित विस्तृत विवरण एवं निविदा शर्तें वेबसाइट www.balrampur.gov.in पर देखी जा सकती है।




सदस्य
जिला निर्माण समिति बलरामपुर
कार्यपालन अभियंता
लोक निर्माण विभाग (वि./यां.) संभाग
अम्बिकापुर (छत्तीसगढ़)

COLLECTOR (ZILA NIRMAN SAMITEE) BALRAMPUR (C.G.)
DISTT. - BALRAMPUR
NIT SCHEDULE FOR PROVIDING ELECTRIFICATION WORK AT HIGH SCHOOL
SEMRI CHOWK COLLECTORATE ROAD & TAHSHIL ROAD SABJI MARKET

PAC Rs. 84.62 Laes

S.No.	SOR. Item No. & Page	Description of Item	Qty.	Unit	Rate	Amount
1	(Item No. 17.2.23 page No. 105)	Supplying and laying following sizes additional one number, PVC insulated/ XLPE, PVC sheathed, steel armoured, aluminium conductor power cable of 1.1 KV grade direct in ground as in the same trench in one tier horizontal formation including excavation, sand cushioning, protective covering and refilling the trench etc as required.4 x 16 sq. mm.				
		High School to semri chowk Collectorate road	3800			
		Tashil Road to Sabji Market	1600			
		Total	5400	Metre	231.00	1247400.00
2	(Item No. 16.2.1 page No. 94)	Supplying and laying HDPE pipe of 4kg/sqcm in ground below road, path etc at a depth not less than 40 cm and upto 90 cm including excavation, dismantling of road if required and refilling the trench with excavated material, ramming and making the surface good etc. as required.63 mm outer dia				
		High School to semri chowk Collectorate road	3500			
		Tashil Road to Sabji Market	1300			
		Total	4800	Metre	140.00	672000.00
3	(Item No. 17.28.3 page No. 117)	Supplying, fixing and cramping suitable size and all type aluminium ferule/ lugs to following size 1.1 KV grade power cable core / lead, pressed with high pressure cramping tool including connection to switch gear/ MCCB etc as required.16 sq. mm				
		High School to semri chowk Collectorate road	950			
		Tashil Road to Sabji Market	240			
		Total	1190	Each	13.00	15470.00
4	(Item No. 5.11.1 page No. 31)	Supplying and drawing following sizes of FR PVC insulated copper conductor, single core cable in the existing surface/ concealed, steel/ PVC conduit/ PVC casing capping as required.1 x 1.5 sq. mm				
		High School to semri chowk Collectorate road	2000			
		Tashil Road to Sabji Market	600			
		Total	2600	Metre	22.00	57200.00
5	(Item No. 14.19 page No. 88)	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing along with existing surface/ concealed conduit/ submain wiring/ cable as required.				
		High School to semri chowk Collectorate road	3300			
		Tashil Road to Sabji Market	1100			
		Total	4400	Metre	20.50	90200.00




S.No.	SOR. Item No. & Page	Description of Item	Qty.	Unit	Rate	Amount
6	(Item No. 21.16.2 page No. 142)	Supplying and fixing water tight terminal box made of 1.6mm thick M.S. sheet with detachable gland plate in bottom, hinged front open able cover, rubber gasket, having 1 Nos 4way connector and 1 No SPMCB inside the box for cable connection, fixed to pole with 2 Nos clamp made from 40x3mm M.S. flat with 2 No nut bolt dully painted with 2 coat of red oxide paint and 2 coat aluminium paint complete as required. 30x20x15 cms.				
		High School to semri chowk Collectorate road	98			
		Tashil Road to Sabji Market	29			
		Total	127	Each	765.00	97155.00
7	(Item No. 21.11.7 page No. 142)	Erection of GI octogonal/ tubular pole on existing cement concrete foundation having grouted bolts and nuts, aligning in true vertical position as required. 9 metre high				
		High School to semri chowk Collectorate road	98			
		Tashil Road to Sabji Market	29			
		Total	127	Each	890.00	113030.00
8	(Item No. 21.12 page No. 142)	Designing and providing suitable RCC foundation in Cement Concrete 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size) for 3 mere to 12 metre high GI octagonal pole including steel reinforcement (minimum 90kg per cum), form work, embedding 2 nos 50mm dia PVC pipe for cable entry in each foundation, excavation disposal of surplus soil and curing etc. as required.				
		High School to semri chowk Collectorate road	98			
		Tashil Road to Sabji Market	29			
		Total	127	cum	4906.00	623062.00
9	(Item No. 8.30.6 page No. 45)	Supplying, installation, testing and commissioning of following 230/250 volts LED street light fitting with all accessories like driver, heat sink made of die cast aluminium with IP 66 protection and 5 KV surge protection on pole bracket complete as required and furnishing 2 Yrs Guarantee certificate from manufacturer. 135 watt				
		High School to semri chowk Collectorate road	98			
		Tashil Road to Sabji Market	29			
		Total	127	Each	22823.00	2898521.00
10	(Item No. 11.10.1 page No. 71)	Supplying and fixing SP MCB, 240 volts, 'B' curve, suitable for lighting and other loads in the existing MCB DB complete with connections, testing and commissioning etc. as required. 6 amps to 32 amps				
		High School to semri chowk Collectorate road	98			
		Tashil Road to Sabji Market	29			
		Total	127	Each	154.00	19558.00


[Handwritten Signature]


S.No.	SOR. Item No. & Page	Description of Item	Qty.	Unit	Rate	Amount
11	(Item No. 16.3.1 page No. 95)	Supplying and laying following size medium class G.I. pipe in ground below road, path etc at a depth not less than 40 cm and upto 90 cm including excavation, dismantling of road if required and refilling the trench with excavated material, ramming and making the surface good etc. as required.50 mm internal dia				
		High School to semri chowk Collectorate road	100			
		Tashil Road to Sabji Market	30			
		Total	130	Metre	367.00	47710.00
12	(Item No. 9.12.2 page No. 54)	Providing and fixing metal clad, TP&N double break fuse switch unit (HRC), 415/500 volts, with H.R.C. fuses including drilling holes on the board, connections, earthing the body etc. as required. (Thimbeling shall be paid separately).100 amps				
		High School to semri chowk Collectorate road	3			
		Tashil Road to Sabji Market	1			
		Total	4	Each	4713.00	18852.00
13	(Item No. 21.9.3 page No. 141)	Supply and fixing following street light pole bracket on existing pole made out of 50 mm dia MS "B" class pipe welded to 300 mm long MS pole canopy of suitable dia at a angle of 102.50 including having MS triangular stiffner of size 150 X 50 X 5 mm thick, making arrangement for tightening the bracket with pole by providing suitable size heavy duty nuts and bolts in canopy, painting with one coat of approved steel primer etc. as required. Single Over Hang 1.50 metre Long				
		High School to semri chowk Collectorate road	98			
		Tashil Road to Sabji Market	29			
		Total	127	Each	1191.00	151257.00
14	(Item No. 21.8.1 page No. 141)	Supply of hot dipped galvanized (in single dip to average 70 micron) octoganal pole made of 3mm thick steel plate having base plate 310x310x16mm, window and flush cover with locking arrangement at suitable height from base for cable termination block, pole suitably reinforced with welded steel section at window cut section to make the strength of pole unaffected, including template and anchor plate 270x270x3mm with 4 nos 20mm dia 750mm long foundation bolts (EN8 grade). 10 metre high, minimum dia 200mm at bottom and 100mm at top				
		High School to semri chowk Collectorate road	98			
		Tashil Road to Sabji Market	29			
		Total	127	Each	18306.00	2324862.00
15	(Item No. 14.4 page No. 88)	Earthing with copper earth plate 600 mm X 600 mm X 3 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe, with charcoal and salt as required.				
		High School to semri chowk Collectorate road	6			
		Tashil Road to Sabji Market	2			
		Total	8	Set	6754.00	54032.00

[Handwritten Signature]

S.No.	SOR. Item No. & Page	Description of Item	Qty.	Unit	Rate	Amount
16	(Item No. 14.10 page No. 88)	Providing and fixing 4.00 mm dia copper wire on surface or in recess for loop earthing as required.				
		High School to semri chowk Collectorate road	90			
		Tashil Road to Sabji Market	30			
		Total	120	Metre	76.00	9120.00
17	(Item No. 32.1 page No.)	Earth work in all type soil except soft rock / hard rock with all lead and 1.5 metre lift, dressing, stacking excavated strata including refilling of excavated soil in trench / pit to ground level complete as required.				
		High School to semri chowk Collectorate road	33.6			
		Tashil Road to Sabji Market	11.2			
		Total	44.8	cum	163.00	7302.40
FOR FEEDER PILLER ARRANGEMENT						
18	(Item No. 9.10.3 page No. 54)	Providing and fixing metal clad, TP&N switch fuse unit (re-wirable), 415/500 volts, with porcelain re-wirable fuses including drilling holes on the board, connections, earthing the body etc. as required. (Thimbeling shall be paid separately). 100 amps				
		Total	4	Each	3306.00	13224.00
19	(Item No. 9.11.4 page No. 54)	Providing and fixing porcelain re-wirable fuse carrier and base unit on wooden board including drilling holes on the board, screws, connections etc. as required. (Thimbeling shall be paid separately). 100				
		Total	4	Each	275.00	1100.00
20	(Item No. 9.13.3 page No. 55)	Providing and fixing bolted connection type following H.R.C. fuses, with 80 KA breaking capacity in existing SFU/ FSU including bolts and nuts etc. as required. 100 amps				
		Total	12	Each	120.00	1440.00
21	(Item No. 22.33 page No. 148)	Supplying and erection DANGER BOARD made MS sheet duly painted and maked as per IE rules and specification.				
		Total	4	Each	56.50	226.00
					Total	8462721.40
					Say Rs.	84.62 Lacs


Sub Engineer
P.W.D. (E/m) Sub Dn.
Ambikapur



Sub Divisional Officer
P.W.D. (E/m) Sub Dn.
Balrampur (C.G.)


Executive Engineer
Zila Nirman Samiti
P.W.D. (E/m) Division
Nodel Officer
Ambikapur (C.G.)

LIST OF APPROVED MATERIAL

- | | | | |
|----|---------------------------------|----|--|
| 1. | <u>Octagonal Pole</u> | :- | I.S.I. Certified with standard guage & Specifications. |
| 2. | <u>Cable</u> | :- | A. Havell's
B. Polycab
C. V. Guard
D. Finolex |
| 3. | <u>Main Switch</u> | :- | A. Standerd
B. L & T
C. Havell's
D. HPL |
| 4. | <u>MCB</u> | :- | A. HPL
B. Havell's
C. Arkaylite |
| 5. | <u>Street Light Fitting LED</u> | :- | A. Bajaj
B. Havell's
C. Mosslight |

Note :- All Other Items to be used should be as per specifications of C.G. P.W.D.


Executive Engineer
P.W.D. (E/M) Division
Ambikapur (C.G.)